

EMC Test Results for WNR-EC2 Columbus Wheel Nut Wrench

1. Machine Information

- **Machine Name:** WNR-EC2 Columbus Wheel Nut Wrench
 - **Manufacturer:** Columbusmaskiner AB
 - **Tested Product Description:** Wheel nut wrench for heavy trucks
-

2. EMC Test Report

2.1 General Information about the Tests

- **Test Date:** December 18, 2024
- **Test Time Interval:** 12:13:42 - 12:14:02
- **Test Leader:** Jari Palosaari
- **Responsible for Machine's CE Marking:** Alexander Österström
- **Test Type:** Electromagnetic Compatibility (EMC)
- **Test Setup:** The test equipment (Combinova FD 10) was placed on a stand approximately 20 cm from the machine during the test.
- **Test Duration:** The test was conducted for about 1 minute to measure average electromagnetic fields.
- **Measurement Range:** Frequency range 10 Hz - 400 kHz
- **Standards Applied:**
 - EN 61000-6-2 (Immunity)
 - EN 61000-6-4 (Emission Requirements)

2.2 Test Equipment and Methodology

- **Measurement Equipment Used:** [Combinova FD 10]
 - **Test Method:**
 - Frequency Range: 10 Hz - 400 kHz
 - Measurement Speed: 1
 - Measurement Mode: B
 - Gain: 1
 - Test Duration: Approximately 1 minute
 - Average Field Measurements: The measurement includes averages for the electromagnetic fields within the specified frequency range.
-

2.3 Test Results

Order No	Status	Peak Value (μT)	X (μT)	Y (μT)	Z (μT)	RMS (μT)	X (μT) RMS	Y (μT) RMS	Z (μT) RMS	Frequency (Hz)
1	Range change	3.2930	1.6612	2.6962	1.5825	0.4959	0.1888	0.3690	0.2722	0
2	OK	2.9749	1.4422	2.5579	1.8429	0.7238	0.2631	0.6116	0.2839	35
3	OK	2.1640	1.1030	1.9453	1.1959	0.5470	0.1964	0.4734	0.1912	17
4	OK	4.8429	4.0862	2.1656	1.7709	0.8291	0.5413	0.5333	0.3316	42
5	OK	4.6136	3.5987	2.4883	1.6282	0.8555	0.5219	0.6279	0.2555	32
6	OK	2.2719	1.0294	1.9373	1.1332	0.4710	0.1516	0.3699	0.2492	40
7	OK	2.0247	0.8183	2.0145	0.8742	0.7829	0.2831	0.6758	0.2758	0
8	OK	2.6769	0.9472	2.3110	1.3124	0.6737	0.2413	0.5766	0.2515	0
9	OK	4.5201	3.6141	2.3413	1.7023	0.8020	0.5383	0.5134	0.2998	36
10	OK	4.1493	3.5244	2.6421	1.7284	0.8032	0.4825	0.5841	0.2670	29
11	OK	4.3693	3.5969	2.2150	1.7087	0.8318	0.4885	0.6194	0.2636	0
12	OK	2.6129	1.4577	2.2211	1.4085	0.5497	0.1820	0.4362	0.2807	41
13	OK	2.0159	0.8097	1.9091	0.5171	0.6818	0.2840	0.5660	0.2526	0
14	OK	2.7382	1.2226	2.1018	1.6412	0.7467	0.2498	0.6417	0.2886	0
15	OK	2.6271	1.3040	2.2340	1.3720	0.5497	0.1854	0.4549	0.2466	34
16	OK	2.1585	0.7444	2.0166	0.5933	0.6282	0.2066	0.5386	0.2487	0
17	OK	4.6503	3.9139	1.8698	1.7882	0.6064	0.4333	0.3207	0.2777	28
18	OK	4.7065	3.6635	2.5428	1.6455	0.7575	0.4771	0.5313	0.2527	28
19	OK	2.1099	1.1803	1.9372	0.6277	0.7673	0.4504	0.5542	0.2806	0
20	OK	4.7674	3.8686	2.0812	1.8985	0.8131	0.5056	0.5759	0.2718	32

Measurement Uncertainty: The measurement uncertainty for the recorded electromagnetic fields is estimated to be $\pm 5\%$, based on the test equipment specifications and standard measurement uncertainty for this type of test.

3. Conclusion

- **Test Results:** The MD-EL2 machine has passed EMC testing within the specified frequency range of 10 Hz to 400 kHz, and the results have been documented according to the standard.
 - **Approval:** The machine meets the electromagnetic compatibility requirements according to applicable standards.
-

4. Approval

- **Test Leader (Name, Title):** Jari Palosaari,
 - Date: December 20, 2024
 - **Responsible for Machine's CE Marking:** Alexander Österström, Technical Manager
Date: December 20, 2024
-

Columbusmaskiner AB

Hejargatan 13

632 29 Eskilstuna

Sweden

Email: info@columbusmaskiner.se

Phone: +46-724 544 244